

Freedom™  
Curb Flashing With Termination Bar  
FD 502

Diagram

Updated: 11/06



*Quality You Can Trust Since 1886...  
From North America's Largest Roofing Manufacturer™*

**RS MAX 10 YR WARRANTY**

REFER TO PARAPET AND WALL  
DETAIL FOR TERMINATION

GAF WATER BLOCK

EVERGUARD® CAULKING

DRILL-TEC™ TERMINATION BAR  
FASTENED 12" O.C.

EVERGUARD® PRIMER

EVERGUARD® FREEDOM  
MEMBRANE

DRILL-TEC™ PLATES & SCREWS  
12" O.C.

HEAT WELDED LAP

EVERGUARD® FREEDOM  
MEMBRANE

ENERGYGUARD™ ROOF  
INSULATION


ROOF DECK/SUBSTRATE

8" min.

ALTERNATE BASE  
REFER TO DETAIL 307

**NOTE:**

1. INCREASED FASTENING TO 6" O.C. MAY BE REQUIRED TO KEEP CONSTANT COMPRESSION OF BAR TO WALL.
2. FOR INSULATION THICKNESS GREATER THAN 8" CONTACT GAFMC CONTRACTOR SERVICES FOR ALTERNATE MEMBRANE ATTACHMENT REQUIREMENTS.
3. TO MAKE A SEAM ON RS WITHOUT RS PRESENT, YOU MUST USE GAF CLEANER AS WELL AS GAF PRIMER TO PREP THE AREA.
4. APPLY EVERGUARD® TPO CUT EDGE SEALANT TO ALL CUT REINFORCED TPO EDGES ( REFER TO DETAIL FD 115 ) AND ALL RS SEAMS.



**CURB FLASHING WITH TERMINATION  
BAR**

FREEDOM RS & HW

DRAWING #

**FD 502**

SCALE

N.T.S.

ISSUE/ REVISION DATE

11-01-06